

DATE PLOTTED: 20 August 2024 2:21 PM BY: JOC MILLER-NORMAN

LANEWAY RECONSTRUCTION WORKS


ROSEMONT LANE

NORWOOD, SA 5067


FOR

CITY OF NORWOOD, PAYNEHAM AND ST PETERS

DRAWING REGISTER	
SHEET NUMBER	SHEET TITLE
0001	FACESHEET, LOCALITY PLAN AND DRAWING REGISTER
1000	LAYOUT PLAN
1010	TREE ROOT LAYOUT PLAN
1100	LANEWAY LONGITUDINAL SECTION
1200	LANEWAY CROSS SECTIONS - SHEET 1 OF 2
1201	LANEWAY CROSS SECTIONS - SHEET 2 OF 2
1300	DRAINAGE LONGITUDINAL SECTION
1301	DRAINAGE DETAILS AND PIT SCHEDULE
1400	TYPICAL DETAILS



LOCALITY PLAN
NTS
GOOGLE MAPS IMAGE (ACCESSED 15/05/2021)



FOR CONSTRUCTION


XREFS: CAD File: C:\Users\joe\OneDrive\Engineering\Dropbox\Dryside\1_Jobs\DSE20058_Rosemont Ln_NPSP4\ENGINEERING\2_Drawings\DSE20058-0001.dwg

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	-	NOT ISSUED AS PART OF DRAWING SET	-	-	-



**City of
Norwood
Payneham
& St Peters**

© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED
[Signature]
ED HENTY 25/07/2024

CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITEWORKS
FACESHEET, LOCALITY PLAN
AND DRAWING REGISTER

DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	AS SHOWN	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1
DSE20058-0001			A

DATE PLOTTED: 16 December 2024 2:54 PM BY: J.MILLER-NORMAN

XREFS: X:\DSE20058-SURV\X:\DSE20058-CONT-E\X:\DSE20058-CONT-D\X:\DSE20058-CONT-D-50
 CAD File: C:\Users\jnorman\OneDrive\Dropbox\Dryside\Jobs\DSE20058_Rosemont Ln_NPSPL4\ENGINEERING\Drawings\DSE20058-1000.dwg



EXISTING GARAGE/DRIVEWAY APRONS
 COUNCIL TO LIAISE WITH PROPERTY OWNERS FOR THE DEMOLITION AND REMOVAL OF EXISTING GARAGE APRONS. PROPOSED LEVELS TO MATCH EXISTING GARAGE FINISHED FLOOR LEVELS

PROPOSED/EXISTING INTERFACE
 INFILL BEHIND EDGE STRIP TO MATCH EXISTING MATERIAL. COUNCIL TO LIAISE WITH PROPERTY OWNERS

EXISTING DOWNPIPES
 DOWNPIPE HEIGHTS TO BE RAISED WHERE REQUIRED TO SUIT DESIGN LEVELS, COORDINATE WITH PROPERTY OWNERS


LEGEND	
	FEATURE SURVEY
	EXISTING CONTOURS MAJOR & LABEL MINOR & LABEL
	PROPOSED CONTOURS MAJOR & LABEL MINOR
	EXISTING FENCELINE
	PROPOSED REMOVABLE/LOCKABLE BOLLARDS
	PROPOSED DRAINAGE PIPE & PIT
	PIT NUMBER
	PROPOSED EDGE STRIP
	PROPOSED WIDE SPOON DRAIN
	EXCAVATION SHORING REQUIRED
	PROPOSED AG DRAIN
	PROPOSED 125mm PN10 PE100 RISING MAIN
	PROPOSED ELECTRICAL CONDUIT
	OVERLAND FLOW DIRECTION
	EXISTING SEWER
	EXISTING POTABLE WATER
	EXISTING GAS
	EXISTING TELECOMMUNICATIONS

	PROPOSED CONCRETE PAVEMENT
	PROPOSED ASPHALT PAVEMENT
	PROPOSED LANEWAY PERMEABLE/POROUS PAVING
	LIFT AND RESET EXISTING PAVERS IN DRIVEWAY AND LAY NEW PAVERS IN LANEWAY
	TOP DRESS WITH MULCH
	SIGNIFICANT / REGULATED STRUCTURAL ROOT ZONE


WARNING
 BEWARE OF UNDERGROUND SERVICES
 THE LOCATION OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

WARNING
 HIGH PRESSURE GAS MAINS IN CLOSE PROXIMITY

CONTRACTOR TO VERIFY EXISTING SERVICES CONNECTION LEVELS PRIOR TO CONSTRUCTION. ANY DISCREPANCIES MUST BE IMMEDIATELY IDENTIFIED AND THE SUPERINTENDENT NOTIFIED PRIOR TO CONSTRUCTION COMMENCING.



INSET A
 SCALE 1:50



FOR CONSTRUCTION

REV	DATE	DESCRIPTION	DES	VER	APP
B	5/12/2024	ROSEMONT ST SERVICES ADDED	JMN	JMN	EH
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	10/03/2023	PRELIMINARY ISSUE	AW	JMN	-

City of Norwood Payneham & St Peters

Scale 1:50 @A1

Scale 1:200 @A1

© Dryside Engineering (Aust) Pty Ltd.
 This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

DRYSIDE ENGINEERING

www.dryside.com.au
 ABN:45639039839

CHECKED
 J.MILLER-NORMAN 4/12/2024
 APPROVED

 ED HENTY 5/12/2024


CITY OF NPSP
 LANEWAY RECONSTRUCTION WORKS
 ROSEMONT LANE, NORWOOD
 SA 5067
 CIVIL SITENETWORKS LAYOUT PLAN

DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	1:200	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1

DSE20058-1000 B

DATE PLOTTED: 20 August 2024 2:21 PM BY: J.MILLER-NORMAN

EXISTING TREE ROOT SCHEDULE							
TREE NUMBER	ROOT NUMBER	DISTANCE FROM TRUNK CENTRE (mm)	DIRECTION FROM TRUNK CENTRE	DEPTH BELOW NATURAL SURFACE (mm)	ROOT DIAMETER (mm)	CONSTRUCTION PROCESS ADVICE	SRZ OFFSET FROM TRUNK CENTRE (mm)
T1	1	1800-2600	EAST	450	100	DO NOT CUT ROOT, STANDARD KERB OVER	
T1	2	1000	EAST	440	40	CAN CUT ROOT, STANDARD KERB OVER	
T1	3	0-700	EAST	370	300	DO NOT CUT ROOT, STANDARD KERB OVER	4370
T1	4	2700	WEST	400	180	DO NOT CUT ROOT, STANDARD KERB OVER	
T2	5	1500	EAST	350	220	DO NOT CUT ROOT, STANDARD KERB OVER	
T2	6	400-1100	EAST	200	700	DO NOT CUT ROOT, BRIDGE KERB OVER	3800
T2	7	750	WEST	400	130	DO NOT CUT ROOT, STANDARD KERB OVER	
T3	-	-	-	-	-	-	3900
T4	8	200-700	EAST	250	360	DO NOT CUT ROOT, BRIDGE KERB OVER	3900
T5	9	800-1700	EAST	200	150	DO NOT CUT ROOT, BRIDGE KERB OVER	
T5	10	700	WEST	450	140	DO NOT CUT ROOT, STANDARD KERB OVER	4200
T6	11	600	EAST	200	90	DO NOT CUT ROOT, BRIDGE KERB OVER	
T6	12	0	CENTRE	400	60	DO NOT CUT ROOT, STANDARD KERB OVER	
T6	13	1200	WEST	250	80	DO NOT CUT ROOT, BRIDGE KERB OVER	3400
T6	14	2900	WEST	150	50	CAN CUT ROOT, STANDARD KERB OVER	



LEGEND


- Feature Survey
- Existing Contours Major & Label
- Existing Contours Minor & Label
- Proposed Contours Major & Label
- Proposed Contours Minor
- Existing Fenceline
- Proposed Removable / Lockable Bollards
- Proposed Drainage Pipe & Pit
- Tree Identification No. (T1)
- Root Identification No. (T1-3)
- Tree Protection Zone (TPZ)
- Structural Root Zone (SRZ)
- Proposed Edge Strip
- Proposed Wide Spoon Drain
- Proposed AG Drain
- Proposed 125mm PN10 PE100 Rising Main
- Proposed Electrical Conduit
- Existing Sewer
- Existing Potable Water
- Existing Gas
- Existing Telecommunications
- Top Dress with Mulch

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATION OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

WARNING
HIGH PRESSURE GAS MAINS IN CLOSE PROXIMITY

CONTRACTOR TO VERIFY EXISTING SERVICES CONNECTION LEVELS PRIOR TO CONSTRUCTION. ANY DISCREPANCIES MUST BE IMMEDIATELY IDENTIFIED AND THE SUPERINTENDENT NOTIFIED PRIOR TO CONSTRUCTION COMMENCING.

TREE ROOT LAYOUT PLAN
SCALE 1:100




TREE ROOT KERB LONGITUDINAL SECTION
SCALE H 1:100 V 1:100


FOR CONSTRUCTION

XREFs: X:\DSE20058-SURV\X-DSE20058-CONT-E\X-DSE20058-BASE\X-DSE20058-CONT-D\X-DSE20058-CONT-D-50
CAD File: C:\Users\jnorman\OneDrive\Dryside Engineering\Dropbox\Dryside\11_Jobs\DSE20058_Rosemont Ln_NPSPA\ENGINEERING\Drawings\DSE20058-1000.dwg

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	-	NOT ISSUED AS PART OF DRAWING SET	-	-	-



© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.






















CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED
[Signature]
ED HENTY 25/07/2024

CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITWORKS
TREE ROOT LAYOUT PLAN


DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	AS SHOWN	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1

DSE20058-1010


LEGEND	
	DESIGN SURFACE
	EXISTING SURFACE



LANEWAY CROSS SECTIONS
SCALE H 1:100m V 1:50m



© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED
[Signature]
ED HENTY 25/07/2024

CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITeworkS
LANEWAY CROSS SECTIONS
SHEET 1 OF 2

FOR CONSTRUCTION









DRAWN A.WARD	DATE 09/03/2023	SCALE AS SHOWN	DATUM MAHD
DESIGNED A.WARD	DATE 09/03/2023	PROJECTION GD2020	SHEET SIZE A1
DSE20058-1200			A

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	10/03/2023	PRELIMINARY ISSUE	AW	JMN	-



DATE PLOTTED: 20 August 2024 2:21 PM BY: JDE MILLER-NORMAN

LEGEND	
	DESIGN SURFACE
	EXISTING SURFACE




LANEWAY CROSS SECTIONS
SCALE H 1:100m V 1:50m

FOR CONSTRUCTION

XREFS: CAD File: C:\Users\jdmiller-norman\OneDrive\Engineering\Dropbox\Dryside\Jobs\DSE20058\Drawings\DSE20058-1200.dwg

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	-	NOT ISSUED AS PART OF DRAWING SET	-	-	-



© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED
J.Miller-Norman
ED HENTY 25/07/2024

CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITeworks
LANEWAY CROSS SECTIONS
SHEET 2 OF 2



DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	AS SHOWN	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1

DSE20058-1201 A


DATE PLOTTED: 20 August 2024 2:21 PM BY: J.DE MILLER-NORMAN

LEGEND - DRAINAGE LONG SECTIONS	
	FINISHED SURFACE
	EXISTING SURFACE
	DRAINAGE SECTION
	SA-C SAND BACKFILL
	PIT NUMBER

PUMP SCHEDULE	
PUMP STATION	
COMPONENTS - 2No.	SUBMERSIBLE VORTEX PUMP ONE WAY CHECK VALVE AND OTHER FITTINGS AS REQUIRED (IE AIR VALVE/PRESSURE CONTROL) LIFTING CHAIN AND STAND AUTO-COUPLING FLOAT OPERATED
PUMP RATE	VARIABLE: MIN 1.0L/S - MAX 10.0 L/S
PUMP CONTROL	PUMP CONTROLLER AND TELEMETRY TO BE MOUNTED WITHIN ELECTRICITY METER CABINET
STATIC HEAD	APPROX. 3.5m
WETTED SUMP	300mm (SUBJECT TO PUMP SPECIFICATION)
PUMP SUMP WELL	2.5m DEEP.
ON/OFF	REFER PUMP STATION TYPICAL DETAIL
RISING MAIN AND MANIFOLD	DN90mm PE100 PN12.5 AND DN125 PE100 PN10
COMMENT	RISING MAIN TO BE CONFIGURED AS PER TYPICAL SCHEMATIC DIAGRAM



DRAINAGE LONGITUDINAL SECTIONS
SCALE H 1:200m V 1:20m



PUMP STATION TYPICAL DETAIL
SCALE 1:20
NOTES:
1. PUMP SELECTION TO ENSURE PUMP NOISE IS LIMITED TO NO GREATER THAN 39.43 DB(A) AS PER THE EPA VIC NOISE LIMITATION REQUIREMENTS FOR RESIDENTIAL AREAS AT NIGHT (2200-0700 HOURS)
2. RISING MAINS AND MANIFOLD TO BE FIRMLY FIXED TO THE WALLS OF THE PUMP WELL TO ENSURE THERE ARE NO PIPE VIBRATIONS
3. PUMPS ARE TO BE FLOAT TRIGGERED UNLESS OTHERWISE SPECIFIED
4. ALL TANK WALLS AND PIPE CONNECTIONS ARE TO BE EPOXY GROUT SEALED AND MADE WATER TIGHT.

FOR CONSTRUCTION			
DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	AS SHOWN	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1
DSE20058-1300			A

XREFS: CAD File: C:\Users\jdnor\OneDrive\Engineering\Dropbox\Dryside\1_Rosemont Ln_NPSP\4\ENGINEERING\Drawings\DSE20058-1300.dwg

REV	DATE	DESCRIPTION	DES	VER	APP
1	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	-	NOT ISSUED AS PART OF DRAWING SET	-	-	-

**City of
Norwood
Payneham
& St Peters**

© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

**DRYSIDE
ENGINEERING**

www.dryside.com.au
ABN:45639039839

CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED

ED HENTY 25/07/2024





CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITEWORKS
DRAINAGE LONGITUDINAL SECTION

DATE PLOTTED: 20 August 2024 2:21 PM BY: J.MILLER-NORMAN



PIT NO	LOCATION		TYPE	INTERNAL		PIT COVER LEVEL	GRATE/COVERS	DEPTH	INLET		OUTLET		COMMENTS	
	EASTING	NORTHING		WD	LEN				DIA	INV LEV	DIA	INV LEV		
PS	283405.180	6132584.890	PUMP STATION - JP	1800	900	57.522	2No. 900x900 CLASS B LOCKABLE COVERS AND FRAME (2-PART COVER)	2.50	1350	55.326			CONSTRUCT 1800x900 PIT AS PER INFRASTRUCTURE SA STD DRG SD305. PIT TO BE INSTALLED WITH PUMPS BY 'PUMPS AND SYSTEMS PTY LTD'. INSTALL STEP IRONS.	
TANK	283412.056	6132585.464	DETENTION TANK - JP	1800	900	57.544	600x600 CLASS D LOCKABLE COVER AND FRAME	2.15	300	56.598	1350	55.395	CONSTRUCT 1800x900 HAUNCHED PIT AS PER DIT STD DRG 4080-1 TYPE'B'	
2	283413.211	6132583.131	DGEP	2100	450	57.490	2No. 900x450 CLASS D DISHED GRATE AND FRAME	0.87	225	56.699	300	56.624	CONSTRUCT NEW PIT AS PER TYPICAL DETAIL	
3	283427.168	6132584.237	GEP	450	900	57.604	900x450 CLASS D DISHED GRATE AND FRAME	0.77	225	56.889	225	56.839	CONSTRUCT NEW PIT AS PER TYPICAL DETAIL	
4	283441.622	6132585.383	GEP	450	900	57.813	900x450 CLASS D DISHED GRATE AND FRAME	0.78	225	57.084	225	57.034	CONSTRUCT NEW PIT AS PER TYPICAL DETAIL	
5	283455.579	6132586.489	GEP	450	900	57.955	900x450 CLASS D DISHED GRATE AND FRAME	0.73			225	57.224	CONSTRUCT NEW PIT AS PER TYPICAL DETAIL	
6	283402.727	6132586.339	GEP	600	600	57.450	600x600 CLASS B GRATE AND FRAME (BOLT DOWN)	0.72				225	56.727	CONSTRUCT NEW PIT AS PER INFRASTRUCTURE SA STD DRG SD305. COVER TO BE SLOPED TO FOLLOWING PAVER LEVEL. LOW SIDE TO BE SET AT 57.45m AHD.
7	-	-	GSEP	600	900	EX	900x450 CLASS D GRATE AND FRAME, PRECAST B2 LINTEL	0.45	125	PE	-	-	CONSTRUCT NEW PUMP MAIN SURCHARGE PIT AS PER TYPICAL DETAIL	
8	-	-	GSEP	600	900	EX	900x450 CLASS D GRATE AND FRAME, PRECAST B2 LINTEL	0.45	125	PE	-	-	CONSTRUCT NEW PUMP MAIN SURCHARGE PIT AS PER TYPICAL DETAIL	

NOTES:

- ALL PITS ARE TO BE TO INFRASTRUCTURE SA OR DIT (DEPARTMENT OF INFRASTRUCTURE AND TRANSPORT) STANDARDS UNLESS NOTED OTHERWISE.
- COVER LEVELS TO BE SET TO MATCH THE FINISHED SURFACE PROFILES AND ADJACENT CONSTRUCTION.
- GSEP = GRATED SIDE ENTRY PIT, DSEP = DOUBLE GRATED ENTRY PIT, GEP = GRATED ENTRY PIT
- ALL PITS IN ROAD RESERVE TO BE FITTED WITH CLASS D COVERS OR GRATES.
- SET OUT RLs ARE TO THE WATER TABLE OF THE KERB WHERE GRATED PITS HAVE BEEN NOMINATED



GRATED SIDE ENTRY PIT 7 AND 8 DETAIL (SURCHARGE PIT)
SCALE 1:NTS




FOR CONSTRUCTION

XREFS: CAD File: C:\Users\joe\OneDrive\Engineering\Dropbox\Dryside\1_Jobs\DSE20058_Rosemont Ln_NPSP\4\ENGINEERING\Drawings\DSE20058-1300.dwg

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	-	NOT ISSUED AS PART OF DRAWING SET	-	-	-



© Dryside Engineering (Aust) Pty Ltd.
This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.










CHECKED
J.MILLER-NORMAN 25/07/2024
APPROVED
ED HENTY 25/07/2024

CITY OF NPSP
LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITeworks
DRAINAGE DETAILS AND PIT SCHEDULE










DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	NTS	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1

DSE20058-1301 A

DATE PLOTTED: 20 August 2024 2:22 PM BY: J.MILLER-NORMAN
 XREFS: X:\DSE20058-TYPICALS
 CAD File: C:\Users\jnorman\OneDrive\Desktop\Dryside\Engineering\Dropbox\Dryside\Jobs\DSE20058-Drawings\DSE20058-1400.dwg



- KERB NOTES:**
- CONCRETE SHALL BE NORMAL CLASS N25 STANDARD STRENGTH GRADE COMPLYING WITH THE REQUIREMENTS OF AS 1379
 - BEDDING TO BE PM2 / 20 OG COMPACTED TO 96% MMDD TO AS1289 METHOD 5.2.1. BEDDING TO EXTEND MIN. 300mm BEHIND BACK OF KERB. THICKNESS MIN. 100mm TO MATCH EXISTING PAVEMENT SUBBASE, WHICHEVER IS GREATER. PM2 / 20 RG TO BE USED ONLY WHEN SPECIFICALLY APPROVED BY COUNCIL.
 - CONCRETE TO BE SMOOTH TROWELLED FINISHED ON TRAY AND KERB.
 - CONCRETE SPONGE FINISHED ON LAYBACK.
 - SHRINKAGE CONTROL JOINTS (TOOLED JOINT) LOCATED AT 2500mm MAXIMUM SPACING. MIN. 50% OF SECTION AREA TO BE CUT. FINISHED WITH TOOLED JOINT 20mm DEPTH TO PRODUCE NEAT GROOVE NOT LESS THAN 5mm WIDE.
 - CONSTRUCTION JOINTS AS REQUIRED TO BE IN ACCORDANCE WITH AS 2876-2000.
 - LINE OF KERB IS USED TO DETERMINE CARRIAGEWAY WIDTHS.
 - WHERE ADJACENT PAVEMENT IS BLOCK PAVED OR CONCRETE, DELETE 25 x 25mm CHAMFER AND REPLACE WITH R5.
 - BACKFILL BEHIND KERB UNTIL FLUSH WITH COMPACTED APPROVED IN-SITU SITE MATERIAL OR PM2 / 20 OG COMPACTED TO 95% MMDD TO AS1289 METHOD 5.2.1.



FOR CONSTRUCTION			
DRAWN	DATE	SCALE	DATUM
A.WARD	09/03/2023	AS SHOWN	MAHD
DESIGNED	DATE	PROJECTION	SHEET SIZE
A.WARD	09/03/2023	GD2020	A1
DSE20058-1400			A

REV	DATE	DESCRIPTION	DES	VER	APP
A	20/08/2024	CONSTRUCTION ISSUE	AW	JMN	EH
2	28/05/2024	DETAILED DESIGN	AW	JMN	-
1	10/03/2023	PRELIMINARY ISSUE	AW	JMN	-

City of Norwood Payneham & St Peters

This plan and the design here within is produced by Dryside Engineering solely for the use and benefit of the client in accordance with the terms and conditions of the signed contract. Dryside Engineering does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

DRYSIDE ENGINEERING

www.dryside.com.au
ABN:45639039839

CHECKED
J.MILLER-NORMAN
APPROVED
ED HENTY

CITY OF NPSP

LANEWAY RECONSTRUCTION WORKS
ROSEMONT LANE, NORWOOD
SA 5067
CIVIL SITING WORKS
TYPICAL DETAILS